

The DAE is a dual key controlled mechanical time delay unit designed to control access to dangerous machines which have a run-down time or where machinery must complete an operating cycle before access is permitted. The DAE is made for applications where the availability of the main power is limited or where the timer needs to be located in a potentially explosive atmosphere.

Operation

The Castell Mechanical Time Delay Units are used in various applications to control access to hazardous areas, where a run-down time of a machinery is required.

DAE Mechanical Time Delay, 30 sec

Key B is trapped in the DAE, key A is held in a key switch while power is on



Insert and turn key A to initiate time run-down. Once completed, release key B



While key B is released, key A is trapped



- When the machine is running, key A is trapped in the key switch controlling the power. Key B is trapped in the mechanical time delay unit. This key is used to access the machine area, once machine has stopped running.
- Key A is released from the key switch and the power supply is switched off. Key A is then inserted and turned in the DAE unit. Once turned, the time delay begins. Key B is held in the DAE until time elapses. Once the time delay has elapsed the indicator bar on the DAE rotates from red to white. Key B can now be turned and removed.
- This traps key A in the DAE, key A cannot be released until key B is returned.

The DAE mechanical time delay unit is available with 30, 60 or 90 seconds time delay as standard versions.

Any time delay within a range betweeen 30 seconds and 55 minutes is available on request.

The time delay must be longer than the machine run-down time.



TEL: +353 (0) 1 4373653 www.concretespares.ie



Usage

The DAE is designed to operate as part of an integrated safety system, controlling access to hazardous areas. A typical example of machine isolation, time delay and access control.



The DAE mechanical time delay unit is not designed for security purposes.

No hazardous substances were used in the manufacture of this product. The product can be disposed of in standard waste.

Installation

The housing of the DAE mechnaical time delay unit should normally be mounted to a panel using suitable fasteners. Please refer to drawing on page 4 for more installation details.



IMPORTANT:

The unit should be mounted using anti-tamper fasteners to prevent unauthorised removal.



The DAE mechanical time delay unit must be installed by a competent and qualified person who has read and understood these instructions. Please retain this document in your technical file.

Maintenance

Periodic visual checks should be carried out by the site manager / safety officer. Do not lubricate lock barrel with oil or grease, use CK Dry Powder Graphite if necessary.



In case of defects beeing detected please contact your nearest Castell Support Department for further actions. Please see Contact section for contact details.



UK Office

United Kingdom

www.concretespares.ie

5 Caulside Drive, Antrim, BT41 2DU TEL: +44 (0) 28 9448 1800 www.concretespares.co.uk

Unit 6, Saint Anthony's Business Park, Ballymount Road, D22 VW95 Ireland TEL: +353 (0) 1 4373653



Technical Data

Temperature rating	Minimum: -40°C [-40°F] ice free for Q & FS Type		
	Maximum: 107°C [224.6°F] Q Type / 140°C [284°F] FS Type		
Type of mounting Surface mount using suitable fasteners (please refer to drawing on page details)			
Weight	3,0 kg		
Material	Mild steel		
MTTF Certification	Available on request		


Application

In a typical application, the DAE mechanical time delay unit is designed to operate as a part of an integrated safety system that controls access to hazardous areas.

The release of the isolation key (key A) from a key switch, e. g. KS20, unterrupts the electrical supply to the machine.

Key A is then placed in the DAE time delay unit and turned, initiating the timer. After completion of the time out period key B can be released (the time delay must be longer than the machine run-down time).

Key B can then be taken to the AIE acess interlock and the door to the machine room can be opened.



EC-Declaration

We, the manufacturers, declare that the components, detailed herein and placed on the market, comply with all the essential health and safety requirements applying to them.

Empowered signatory:

Mr T.C. Whelan Managing Director





www.concretespares.ie




Drawing

Dimensions:

Note: For safe mounting, use security screws

DAE





www.concretespares.ie



Order Information

	Product Type		1	2		3
Part Number	DAE	-] -	
Example	DAE	-	FS	В]-	30
	4					
	А					
	5					
	В					

1	Lock portion type	FS ⁽¹⁾ / Q ⁽¹⁾
2	Material	B = Brass
3	Time delay	30, 60 or 90 sec (as standard) or as required (max. 30min)*
4	Lock portion symbol: Top lock symbol (Free key symbol)	FS ⁽¹⁾ up to 3 digits / Q ⁽¹⁾ up to 6 digits
5	Lock portion symbol: Bottom lock symbol (Trapped key symbol)	FS ⁽¹⁾ up to 3 digits / Q ⁽¹⁾ up to 6 digits

(1) FS - Lock type Up to 3 symbols

Q - Lock type Up to 6 symbols







^{*} The time delay of the DAE unit must be longer than the machine run-down time

Accessories

Special construction available upon enquiry

Product	Part number
Flip Cap	FLIP-S

Contact Information

